

NOTES:

- SIDEWALK WIDTH SHALL BE 5' WHEN ADJACENT TO BLOCK WALL OR OTHER OBSTRUCTION. FOR BLOCK WALL LOCATION AT INTERSECTION SEE STANDARD 302.
- THE DETECTABLE WARNING SURFACE SHALL BE CONSTRUCTED BY CAST-IN-PLACE METHOD OR SHALL CONSIST OF A PREFABRICATED SURFACE, APPROVED BY THE ENGINEER. A GLUE DOWN DETECTABLE WARNING SURFACE IS NOT ALLOWED. COLOR SHALL BE YELLOW CONFORMING TO FEDERAL STANDARD 595B, COLOR NUMBER 33538, OR AS APPROVED BY THE ENGINEER.
- FOR RIGHT OF WAY LOCATION SEE PROJECT PLANS.

BCR = BEGIN CURB RETURN

= CURB FACE

DWS = DETECTABLE WARNING SURFACE

ECR = END CURB RETURN

EJ = EXPANSION JOINT

= GRADE BREAK GB

MAX = MAXIMUM


MIN = MINIMUM

= TOP OF CURB TC

WPJ WEAKENED PLANE JOINT

TYP = TYPICAL

= EXPANSION JOINT





SAN BERNARDINO COUNTY DEPARTMENT OF PUBLIC WORKS

CURB RETURN WITH SIDEWALK RAMP

BRENDON P. BIGGS, PE DIRECTOR OF PUBLIC WORKS/ROAD COMMISSIONER

> 110 1 OF 2






TRUNCATED DOME PATTERN

DETECTABLE WARNING SURFACE

TRUNCATED DOME DETAIL

RAISED TRUNCATED DOME



SECTION A-A

NOTES:

- 1. THE SIDEWALK AND RAMP THICKNESS SHALL BE 4" MINIMUM.
- 2. THE RAMP RUNNING SLOPE SHALL BE 7.5% MAXIMUM.
- 3. THE CROSS SLOPES OF RAMP, LANDING, AND SIDEWALK SHALL BE 1.5% MAXIMUM.
- 4. THE RAMP SHALL HAVE A TRAVERSE BROOM FINISH TEXTURE ROUGHER THAN THE SURROUNDING SIDEWALK.
- 5. TRANSITIONS FROM RAMPS TO WALKS, GUTTER OR STREETS SHALL BE FLUSH AND FREE OF ABRUPT CHANGES.
- THE MAXIMUM SLOPE OF THE ROAD SURFACE IMMEDIATELY ADJACENT TO THE CURB RAMP SHALL NOT EXCEED 5% WITHIN FOUR FEET (4') OF THE RAMP.
- 7. THE EDGE OF THE DETECTABLE WARNING SURFACE NEAREST THE STREET SHALL BE BETWEEN 5" TO 8" FROM THE GUTTER FLOW LINE.
- 8. MODIFICATIONS TO LOCATION OR DIMENSIONS OF RAMP SHALL REQUIRE APPROVAL OF THE ENGINEER AND SHALL BE SHOWN ON APPROVED PLANS.
- 9. UTILITY PULL BOXES, MANHOLES, VAULTS AND ALL OTHER UTILITY FACILITIES WITHIN THE BOUNDARIES OF THE CURB RAMP WILL BE RELOCATED OR ADJUSTED TO GRADE BY THE OWNER PRIOR TO OR IN CONJUNCTION WITH CURB RAMP CONSTRUCTION.



SAN BERNARDINO COUNTY DEPARTMENT OF PUBLIC WORKS

CURB RETURN WITH SIDEWALK RAMP

BRENDON P. BIGGS, PE DIRECTOR OF PUBLIC WORKS/ROAD COMMISSIONER

> 110 2 OF 2